



Notes:

Electrical and Communications in Workstation Area and Conference Room to be placed in floor and along all walls where furniture indicated.

HVAC should be run along the East wall (opposite windows).

Window Replacements should be 5 equal panes with integral blinds between columns to coincides with office closet width.

All glass wall panels indicated would be floor to ceiling.